

QUOTE from Universal Cryogenics

JOB CODE	Date	Quote #	
OBCOFG08K	6/29/2009	793	

UNIVERSAL CRYOGENICS 1815 W. Gardner Ln. Tucson, AZ. 85705 520-622-6277 ph 520-623-3167 fx www.ucryo.com kirby@ucryo.com

QUOTE VALID FOR 30 DAYS.	Ship To
DAYS.	OBERLIN COLLEGE
SHIPPING WILL BE ADDED TO FINAL INVOICE.	DEPT PHYSICS AND ASTRONOMY 110N PROFESSOR ST
PROGRESS PAYMENTS MAY APPLY WITH PO	OBERLIN OH. 44074

Customer Name / Address

OBERLIN COLLEGE DEPT PHYSICS AND ASTRONOMY 110N PROFESSOR ST OBERLIN OH. 44074

Customer Contact	Customer Contact Ph	Rep	Project
CHRIS MARTIN		KH	

Line	Item	Description	Qty	Rate	Total
1	Dewar	SUPERCAMERA II DEWAR -Rectangular dewar case with coversInternal outer and inner radiation shieldsInternal rigid supportsDewar Cart.	1	75,000.00	75,000.00
2	Cryo-Co	CRYOCOOLERS -Sumitomo SRDK-415D cryocooler with helium potSumitomo CH-208R cryocooler.	1	65,000.00	65,000.00
3	Cryo-Co	CRYOCOOLERS INTERFACE VACUUM -Welded bellows for SRDK-415DWelded bellows for CH-208R. THERMAL -Gold plated copper straps from 1st and 2nd stage SRDK-415DGold plated copper straps from 1st and 2nd stageCH-208Rbaffling 1st stage region.	1	15,000.00	15,000.00

UNIVERSAL CRYOGENICS TERMS AND CONDITIONS 2009 APPLY, THANK YOU FROM UNIVERSAL CRYOGENICS!

Total



QUOTE from Universal Cryogenics

JOB CODE	Date	Quote #	
OBCOFG08K	6/29/2009	793	

UNIVERSAL CRYOGENICS 1815 W. Gardner Ln. Tucson, AZ. 85705 520-622-6277 ph 520-623-3167 fx www.ucryo.com kirby@ucryo.com

QUOTE VALID FOR 30	Ship To
DAYS.	OBERLIN COLLEGE
SHIPPING WILL BE ADDED TO FINAL INVOICE.	DEPT PHYSICS AND ASTRONOMY 110N PROFESSOR ST
PROGRESS PAYMENTS	OBERLIN OH. 44074

Customer Name / Address

OBERLIN COLLEGE DEPT PHYSICS AND ASTRONOMY 110N PROFESSOR ST OBERLIN OH. 44074

Customer Contact	Customer Contact Ph	Rep	Project
CHRIS MARTIN		KH	

Line	Item	Description	Qty	Rate	Total
4	Wiring	INTERNAL WIRING	1	60,000.00	60,000.00
		-Qty 8 gold plated annealed OFHC mixer block bus bar -qty 56 SMA coax Stainless Steel UT-085 series with SMA nut on one end, GPPO bulkhead connector on other end.			
		-Solder Omnetics 51 and 25 pin connectors to DB-51 connectors (provided), qty 8 -Heat sink qty 56 SMA coax at 77K and 15K -Install qty 8 cryo wire assemblies			
		-Additional modifications as needed -qty-12 55-pin hermetic connectors mounted on blank flanges.			
		-qty-3 DT-470-SD-12 temp sensors with internal wiringqty-3 Firerod cartridge heaters with internal wiringheat sinks all wiring on CH-208R 2nd stage.			
5	Dewar	-Cryo-wire supplied by UCRYO. DESIGN		5,000.00	5,000.00
		-Dewar designCorrespondence with customer at UofADewar Leak Checking, Vacuum and Cryogenic Testing of Dewar with Documentation.		,,,,,,,,,,	,,,,,,
6	DELIV	DELIVERY OF SYSTEM IS 5 MONTHS ARO.			
		-FINAL INTERNAL WIRING DETAILS MAY REQUIRE RE-QUOTING.			

UNIVERSAL CRYOGENICS TERMS AND CONDITIONS 2009 APPLY, THANK YOU FROM UNIVERSAL CRYOGENICS!

Total

\$220,000.00